



GENERAL NOTES

1. REFER TO M-001 FOR MECHANICAL ABBREVIATIONS, LEGEND, SYMBOLS, AND GENERAL NOTES.
2. COMPONENTS SHOWN DASHED ON THIS DRAWING ARE ITEMS TO BE DEMOLISHED; HALF-TONE COMPONENTS ARE EXISTING-TO-REMAIN.
3. PRIOR TO ANY DEMOLITION ACTIVITIES, SUBCONTRACTOR MUST COORDINATE WITH THE STR TO REVIEW FACILITY ES&H DOCUMENTS, EQUIPMENT TO BE REMOVED, MATERIALS TO BE REMOVED OR DISTURBED, AND IDENTIFY A PLAN PRIOR TO COMMENCING THE WORK. ITEMS TO REVIEW INCLUDE BUT ARE NOT LIMITED TO THE FOLLOWING: NEW WORK IN DISTURBING EXISTING WALLS, FLOORS, ROOFS, OR CEILINGS; ALL CUTTING OR DRILLING; ALL DEMOLITION; REMOVAL AND DISPOSAL.
4. CUT, REMOVE, AND LEGALLY DISPOSE OF ALL MECHANICAL ITEMS SELECTED FOR DEMOLITION AND ANY MECHANICAL ITEMS MADE OBSOLETE BY THE NEW WORK, INCLUDING EXISTING EQUIPMENT/PIPE/TUBE SUPPORTS AND HANGERS.



KEYED NOTES

- ① REMOVE AND DISPOSE OF EXISTING ROOFTOP AIR CONDITIONING UNIT, PIPING, DUCT AND UTILITY CONNECTIONS, SUPPORTS, ANCHORAGE, AND ALL APPURTENANCES. INFILL EXISTING ROOF OPENINGS EXPOSED BY REMOVAL OF ROOFTOP ACHPS UNIT AND SEAL WATER TIGHT PER ARCHITECTURAL AND STRUCTURAL DRAWINGS AND SPECIFICATIONS. REFER TO F3 / A-501 AND S-512.
- ② REMOVE AND DISPOSE OF EXISTING DUCTWORK THROUGH ROOF TO OFFICE SPACE BELOW. REFER TO MD404 FOR CONTINUATION.
- ③ EXISTING ROOFTOP CATWALK, FLOOR GRATING, AND RAILINGS TO REMAIN.
- ④ EXISTING LADDER TO ROOF AND LADDER SUPPORTS TO REMAIN AS IS.

KEY PLAN

F1 MECHANICAL DEMO ROOF PLAN
 MD120 SCALE: 3/32" = 1'-0"
 0 8' 16' 24'
 3/32" = 1'-0"

Sheet Title
**MECHANICAL DEMOLITION
 ROOF PLAN**

Dwg. No.
PLM2021-0432-0005D

Sht. No.
MD120